

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		Potential Projects for DRAFT Complete Streets Prioritization Plan - June 24, 2025		Safety				Connectivity to Destinations				Network Connectivity	
2		Project Name	Project Description	> 2 crashes source: MassDOT	Volume > 3000 AADT source: MassDOT	1/2 mile of K-12 Schools	1/4 mile of K-12 Schools	1/4 mile to Commercial Areas: Wellsley Square, Linden Square, Wellesley Hills, Fells Block and Lower Falls	1/4 mile of Main, Hills, Fells Libraries	1/4 Trail heads and Recreation lands	1/2 to MBTA Train Station	Gap of < 1000 feet	TOTAL - Guiding Score
3													
4	1												
5	2	No Right on Red at Hardy Elementary School Driveway	Install pedestrian activated no-right on red sign at the Weston Road / Hardy School Driveway signal.	1	1	1	1	1	1	1		1	8
6	3	Pedestrian Safety Improvements at Washington and Forest	Install pedestrian activated "No Right On Red" for right turn from Forest onto Washington. Conduct intersection study to confirm appropriate pedestrian delay.	1	1	2		1		1	1	1	8
7	4	Uphill Bike Lane on Washington Street	Add Bike lane on the westbound / uphill side of Washington Street from Glen Road to the Newton TL.	1	1	1	1	1	1		1	1	8
8	5	Mid-block crosswalk improvements on Washington Street at 610 Washington Street near Denton and 672 Washington Street near Upland	Install RRFB and add double sided yellow-green crosswalk signs (W11-2, w16-6P, W16-7P); Trim branches. Install advanced warning signs with yellow-green advanced warning pedestrian ahead sign (S1-1, W16-9P) to be approximately 300ft in front of the crosswalk .	1	1	1		1	1	1	1	1	8
9	6	Crosswalk Safety Improvements at Rockland and Linden	Add dashed double yellow line continuing through intersection to show through direction. Add RRFB, relocate crosswalk and ped warning signs. (Difficult to see pedestrian over the bridge)	1	1	1		1		1	1	1	7
10	7	School Zone improvements	Upgrade school zone signs with MUTCD Compliant School Speed Limit Assembly (S4-1P, S4-2P, S4-3P, S4-4P, S4-6P, S5-1), END SCHOOL SPEED LIMIT Sign (S5-3) with speed feedback radar sign, yellow green signs and led flashing lights on Grove Street (2) along Dana Hall and Ten Acre Schools' frontage and Kingsbury Street (2) along Wellesley Middle School frontage.	1	1	1	2			1		1	7
		Fuller Brook Path Crosswalk Safety Improvements	Fuller Brook Crossing at Brook Street - add RRFB and double-sided yellow green signs with advance warning signs; remove existing children sign on Brook; Fuller Brook Crossing at Grove Street - add advanced warning signs; Fuller Brook Crossing at Wellesley Avenue - add RRFB and double-sided arrows to existing ped signs; Fuller Brook Crossing at Abbot Road - install RRFB.	1	1	1		1		1	1	1	7

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		Potential Projects for DRAFT Complete Streets Prioritization Plan - June 24, 2025		Safety				Connectivity to Destinations				Network Connectivity	
2		Project Name	Project Description	> 2 crashes source: MassDOT	Volume > 3000 AADT source: MassDOT	1/2 mile of K-12 Schools	1/4 mile of K-12 Schools	1/4 mile to Commercial Areas: Wellsley Square, Linden Square, Wellesley Hills, Fells Block and Lower Falls	1/4 mile of Main, Hills, Fells Libraries	1/4 Trail heads and Recreation lands	1/2 to MBTA Train Station	Gap of < 1000 feet	TOTAL - Guiding Score
3													
11	8	Crosswalk Enhancements on Wellesley Avenue at Clifford	Install RRFB.	1	1	1	1			1	1	1	7
12	9	Crosswalk across State Street at Atwood	Install ADA compliant crosswalk across State at Atwood with double sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P)	1	1	2	1			1		1	7
13	10	Fisk Elementary School Safety Improvements mid-block Cedar Street at Fiske Elementary School Path	Replace yellow flashers with pedestrian activated led RRFB's; add double sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P); relocate poles to be on the upstream traffic direction for better visibility of students standing in crosswalk. Trim branches. Relocate and replace old advanced warning signs with yellow-green advanced warning pedestrian ahead sign (S1-1, W16-9P) to be approximately 300ft ahead of the crosswalk. Add MUTCD Compliant School Speed Limit Assembly (S4-1P, S4-2P, S4-3P, S4-4P, S4-6P, S5-1), END SCHOOL SPEED LIMIT Sign (S5-3) with speed feedback radar sign. Place School Speed Limit Ahead (S4-5) signs approximately 200 to 500 feet ahead of the school zone.	1	1	1	1			1		1	6
14	11	Weston Road Linden Road Intersection	Install full signal with pedestrian phases; Add left turn lane on Weston. Land taking voted at STM 2024	1	1			1		1	1	1	6
15	12	Pedestrian Improvements at Oak Street/Ivy Road/ Pinewood Road	Install new ADA compliant crosswalk with double-sided yellow green signs (W11-2, W16-6P, W16-7P), slightly south of existing crosswalk (remove existing). Remove pavement on both sides of Pinewood Road at Oak Street to "square off" intersection. Remove pavement in the northwest corner of Ivy and Oak to "square off" intersection.	1	1	2	1					1	6
16	13	Wellesley Avenue Bike Lane	Stripe ~1570 feet of bike lanes from Amherst Road to existing bikes lanes at the intersection of Great Plain Avenue on both sides and stripe ~1,405 feet of uphill bike lane from Great Plain Avenue to Whiting Road with striping and signs indicating bike lane ends, cyclists share the road.	1	1	1			1	1	1		6

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		Potential Projects for DRAFT Complete Streets Prioritization Plan - June 24, 2025		Safety				Connectivity to Destinations				Network Connectivity	
2		Project Name	Project Description	> 2 crashes source: MassDOT	Volume > 3000 AADT source: MassDOT	1/2 mile of K-12 Schools	1/4 mile of K-12 Schools	1/4 mile to Commercial Areas: Wellsley Square, Linden Square, Wellesley Hills, Fells Block and Lower Falls	1/4 mile of Main, Hills, Fells Libraries	1/4 Trail heads and Recreation lands	1/2 to MBTA Train Station	Gap of < 1000 feet	TOTAL - Guiding Score
3													
17	14	Complete Hastings Street Near Fiske School	Build ~140 feet of new sidewalk and new road to create safer pedestrian and vehicle circulation at Fiske Elementary School	1	1	1	1			1		1	6
18	15	Safety Improvements Benvenue Street / Grove Street Intersection	Install two radar activated flashing stop signs on Benevenue and two radar activated flashing yellow intersection warning signs. Secure easement to remove stone wall and vegetation including a public shade tree to increase sightlines for both pedestrians and vehicles.	1	1	2				1		1	6
19	16	Benvenue Street Sidewalk (West)	Add ~530 feet of sidewalk along Benvenue Street; add new ADA compliant crosswalk with double sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P) connecting to the Sudbury Aqueduct Path	1	1	1	1			1		1	6
20	17	Pedestrian Refuge at Washington Street and Cliff Road	Align Cliff and Seaward Roads at the intersection with Washington Street to create larger pedestrian refuge for crossing and smoother traffic control within the intersection.	1	1	1		1		1	1		6
21	18	Pedestrian Activated No Right On Red at Walnut / Cedar	Install a pedestrian activated no right on red at the Walnut Cedar Intersection	1	1	1	1			1			5
22	19	Oakland Street Crosswalk	Install ADA compliant crosswalk across Oakland at the Longfellow Trail parking lot, Centennial Trails and Jackson Road with double-sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P) and ~ 100 feet of sidewalk.	1	1	1				1		1	5
23	20	Crosswalk on Weston Road at Norfolk Terrace	Secure easement and install ADA compliant crosswalk with double-sided yellow green pedestrian signs (W11-2, W16-6P, W16-7P)	1	1			1		1		1	5

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		Potential Projects for DRAFT Complete Streets Prioritization Plan - June 24, 2025		Safety				Connectivity to Destinations				Network Connectivity	
2		Project Name	Project Description	> 2 crashes source: MassDOT	Volume > 3000 AADT source: MassDOT	1/2 mile of K-12 Schools	1/4 mile of K-12 Schools	1/4 mile to Commercial Areas: Wellsley Square, Linden Square, Wellesley Hills, Fells Block and Lower Falls	1/4 mile of Main, Hills, Fells Libraries	1/4 Trail heads and Recreation lands	1/2 to MBTA Train Station	Gap of < 1000 feet	TOTAL - Guiding Score
3													
24	21	Dover Road Sidewalk	Add ~134 feet of sidewalk, retaining wall and safety rail along easterly side of Dover Road from Benvenue to the Sudbury Aqueduct Trail; add one (1) ADA compliant mid block crosswalk with RRFB and double sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P) advanced signs at the Sudbury Aqueduct. Add ~1560 feet of sidewalk on the westerly side of Dover Road to Gove Street with one (1) ADA compliant crosswalk across Stonefield Lane ; one (1) ADA compliant crosswalk across Livingston Road and a new ADA compliant RRFB crosswalk across Grove Street to connect to existing sidewalk.	1	1	1				1		1	5
25	22	Laurel Avenue Sidewalk	Add ~575 feet of sidewalk through town land along Laurel Avenue from 25 Laurel Avenue to Forest Street connecting existing sidewalk.	1		1		1		1		1	5
26	23	Hunnewell Sidewalk	Add ~1,180 feet of sidewalk on Hunnewell Street from 61 Hunnewell Street to the Needham TL and Install new ADA compliant crosswalk with double-sided yellow green signs (W11-2, W16-6P, W16-7P)at the Sudbury Aqueduct Trail crossing.	1	1	1				1		1	5
27	24	Crest Road Sidewalk	Add ~525 feet of sidewalk on the northern side of Crest Road between Summit Road and Curve Street.	1					1	1	1	1	5
28	25	Carlton Road Sidewalk Gap	Add ~242 feet of sidewalk from 7 Carleton Road to Brook Street connecting existing sidewalk.			2	1			1		1	5
29	26	Pine Tree Sidewalk Gaps	Add ~353 feet of side walk in front of 5,7,21-25 Pine Tree Road and 4 Highland Road.			1	1	1			1	1	5

	A	B	C	D	E	F	G	H	I	J	K	L	M			
1		Potential Projects for DRAFT Complete Streets Prioritization Plan - June 24, 2025							Safety			Connectivity to Destinations			Network Connectivity	
		Project Name	Project Description	> 2 crashes source: MassDOT	Volume > 3000 AADT source: MassDOT	1/2 mile of K-12 Schools	1/4 mile of K-12 Schools	1/4 mile to Commercial Areas: Wellsley Square, Linden Square, Wellesley Hills, Fells Block and Lower Falls	1/4 mile of Main, Hills, Fells Libraries	1/4 Trail heads and Recreation lands	1/2 to MBTA Train Station	Gap of < 1000 feet	TOTAL - Guiding Score			
2																
3																
30	27	Linden Street Crosswalk at Upwey	Add ~ 1495 feet of sidewalk on the northerly side of Linden Street. Install a mid-block ADA compliant crosswalk across Linden Street with double sided yellow-green crosswalk signs (W11-2, w16-6P, W16-7P). Install new ADA compliant crosswalks at Upwey, and both Kirkland Circle intersections. Remove pavement at Upwey Road and Linden Street; both Kirkland Circle and Linden Street Intersections to tighten the corner radii and reduce crossing distance.	1	1	1					1	1	5			
31	28	Benvenue Street Sidewalk (east)	Add ~1425 feet of sidewalk along Benvenue Street between Lathrop Road and Brook Street and ADA compliant crosswalks across Lathrop Road; Brook Street, and Benvenue Street to connect to existing sidewalk.	1	1	2				1			5			
32	29	Crosswalk Improvements	Upgrade Crosswalks - install RRFB's on Forest at Whiting; on Washington Street at Croton; on Grove at Longmeadow and add second pedd crossing sign in front of telephone pole on Grove.	1	1	1				1	1		5			
33	30	Hastings Street Sidewalk Gap	Add ~406 feet of sidewalk from Cedar Street Sidewalk through 15 Hastings Street to connect to existing Hastings sidewalk.	1	1	1	1			1			5			
34	31	Crosswalk Improvements - Cliff	Install RRFB with double sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P) at the existing Cliff Road crosswalk at Garden Road.	1	1	1				1	1		5			
35	32	Hilltop Sidewalk Gap	Add ~170 feet of sidewalk in front of numbers 17, 19, 25 Hilltop to fill sidewalk gap.			1	1	1			1	1	5			
36	33	Bacon Street Sidewalk	Add ~792 feet of sidewalk on the southern side of Bacon Street between Central Street and Natick TL	1	1					1		1	4			
37	34	Great Plain Sidewalk	Add ~740 feet of sidewalk on the easterly side of Great Plain Avenue from 130 Great Plain Avenue to the driveway of 150 Great Plain Avenue.	1	1					1		1	4			
38	35	Crosswalk improvements on Forest Street at Abbott Road	Relocate new ADA compliant crosswalk ~ 20 feet north on Forest Street (remove existing crosswalk) and add double sided yellow-green crosswalk signs (W11-2, w16-6P, W16-7P).	1	1					1		1	4			

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		Potential Projects for DRAFT Complete Streets Prioritization Plan - June 24, 2025		Safety				Connectivity to Destinations				Network Connectivity	
2		Project Name	Project Description	> 2 crashes source: MassDOT	Volume > 3000 AADT source: MassDOT	1/2 mile of K-12 Schools	1/4 mile of K-12 Schools	1/4 mile to Commercial Areas: Wellesley Square, Linden Square, Wellesley Hills, Fells Block and Lower Falls	1/4 mile of Main, Hills, Fells Libraries	1/4 Trail heads and Recreation lands	1/2 to MBTA Train Station	Gap of < 1000 feet	TOTAL - Guiding Score
3													
39	36												
		Crosswalk Improvements on Glen Road at RR Bridge	Install pedestrian activated RRFB's; Add ADA compliant ramps with tactile pads	1	1					1		1	4
40	37	Washington Street Trail Connection Crosswalk	Add ~410 feet of sidewalk easterly of 828 Washington Street to meet with the existing Trail easement and install new ADA compliant crosswalk with RRFB with double sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P) and advanced warning signs	1	1					1		1	4
41	38	Wellesley Avenue Sidewalk	Add ~2190 feet sidewalk along Wellesley Avenue from 180 Wellesley Avenue to Forest Street. Add mid-block ADA compliant crosswalk with double sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P) to connect to existing sidewalk.	1	1	1				1			4
42	39	Pedestrian Improvements at the Sprague Road / Lowell Road Intersection	Add ~ 250 ft of new sidewalk on the southwest side of Lowell Street from 198 Lowell Road to the Sprague Road intersection and add a new ADA compliant crosswalk with double sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P) across Sprague Road connecting to the existing sidewalk. Remove pavement on both sides of Sprague at the intersection to reduce turning radii and pedestrian crossing distance.			2	1					1	4
43	40	Avon Sidewalk	Add ~1525 feet of sidewalk along Avon Road between Curve Street and Weston Road; Add new ADA compliant crosswalk across Maurice Road.	1		1				1	1		4
44	41	Forest Street Sidewalk Gap	Add ~512 feet of sidewalk on south side of Forest connecting the Brook Path to the Paine Street Sidewalk	1		1				1	1		4
45	42	Oakland Sidewalk (South)	Add ~2570 feet of sidewalk along Oakland Street and ~600 of retaining wall, connecting the to existing Hunnewell sidewalk to trail system.	1	1	1				1			4
46	43	Oakland Sidewalk (North)	Add ~3,080 feet of sidewalk along Oakland Street connecting the existing sidewalk to trail system. Install ADA compliant crosswalk at Standish Road with double sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P)	1	1	1				1			4

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		Potential Projects for DRAFT Complete Streets Prioritization Plan - June 24, 2025		Safety				Connectivity to Destinations			Network Connectivity		
		Project Name	Project Description	> 2 crashes source: MassDOT	Volume > 3000 AADT source: MassDOT	1/2 mile of K-12 Schools	1/4 mile of K-12 Schools	1/4 mile to Commercial Areas: Wellsley Square, Linden Square, Wellesley Hills, Fells Block and Lower Falls	1/4 mile of Main, Hills, Fells Libraries	1/4 Trail heads and Recreation lands	1/2 to MBTA Train Station	Gap of < 1000 feet	TOTAL - Guiding Score
2													
3													
47	44	Lowell Street Sidewalk	Add sidewalk on Lowell Street from Cliff Road to 12 Lowell Street ( ~329 feet) and from 22 Lowell to Edmunds Road ( ~574 feet) and a ADA compliant crosswalk across Edmunds to connect to existing sidewalk sections. ( ~903 feet total)	1						1	1	1	4
48	45	Suffolk Road Sidewalk and Nantucket Road Sidewalk Gap	Add ~1500 feet of sidewalk along westerly side of Suffolk Road between Bristol and Nantucket. And add sidewalk on the both sides of Nantucket from Suffolk to 7 and 8 Nantucket approximately ~170' and ~340 feet for total of ~2010 feet of sidewalk			1	1			1			3
49	46	Eaton Court Sidewalk	Add ~342 feet of sidewalk along Maugus Avenue between 12 and 18 Maugus Avenue and ~305 feet of sidewalk along Eaton Court from Maugus Avenue to 18 Eaton Court and ADA Compliant crosswalk on Maugus at Eaton Court for total of ~647 feet of sidewalk.						1		1	1	3
50	47	Crosswalk on Paine	Install ADA compliant crosswalk with double sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P) at 33 Paine to connect existing sidewalk to Brook Path and high school pedestrian access.			1	1			1			3
51	48	Seaver Street at Peck Avenue Crosswalk	Install ADA compliant crosswalk with double sided yellow-green crosswalk signs (W11-2, W16-6P, W16-7P) across Seaver Street at Peck Avenue.			1	1					1	3
52	49	Woodlawn Avenue Sidewalk	Add ~750 feet of sidewalk along easterly side of Woodlawn from Hundreds to Colburn.							1	1	1	3
53	50	Albion Road Sidewalk	Add ~ 515 feet of sidewalk along the southerly side of Albion Road from 30 Albion Road to Edmunds Road and add ADA compliant crosswalks on Woodcliff, Albion at Wood Cliff and Edmonds.							1		1	2
54	51	New Crosswalk on Garden at Lanark	Install ADA compliant crosswalk across Garden Road with double sided yellow-green crosswalk signs (W11-2, w16-6P, W16-7P). Remove pavement in the NW corner to reduce corner radii.							1		1	2

[illegible]



[illegible]